



FIDDLEHEAD^{LLC}

BETTER OUTDOOR LIVING

4927 NE Going St • Portland, OR 97218 • LCB# 8670
Tel 503 867 9520 • info@fiddleheadlandscapes.com

Richmond Elementary
Mudhill Planting and flat work proposal
2276 SE 41st. Ave.
Portland, Or 97214

- Excavate hillside as per plan and create 3/4- gravel footing. Haul away soil as necessary. **1,600.00**
- Approx. 25 tons of Columbia River basalt boulders delivered and placed per plan @ 450.00/ton. **11,250.00**
- Backfill between boulders with 1.5" open gravel and top with decomposed granite plus clean up behind heavy equipment. **750.00**
- Skid Steer rental 1wk. **650.00**
- Excavate for synthetic turf and brickwork per plan. Build brick landing to grade with existing asphalt. Use Mutual Materials or similar approved brick, dry-set in herringbone pattern with brick border. Retain using snap-edge paver edging. Approx. 600 sq ft. *not to exceed **15,000.00**
- Place approx. 3.5 tons of Columbia River basalt boulders in addition to amphitheatre boulders, delivered and placed per plan @ 450.00/ton. **1,575.00**
- Deliver approx. 3 units of three way soil blend (from Mt. Scott Fuel) to be moved by volunteers. **750.00**
- Install synthetic turf per plan in center of amphitheatre. Minimum 200 sq ft @ 12.00/ft. **2,400.00**

Total for project 33,975.00

The above work will be completed for the sum of **33,975.00** . A deposit of 17,000.00 is due before the start of work. Progress payment of due once amphitheatre is complete. Second progress payment of due once brick work is complete. Remaining balance due upon completion.

Estimated start day of 6/1/20. Project will take approx. 4 weeks.

Fiddlehead LLC

Date

Client Signature

Date

Fiddlehead llc is licensed by the state landscape contractor's board of Oregon 2111 Front St. NE Salem, Or 97301 503-378-5909

General Terms and Conditions

*All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders and will become an extra charge over and above the estimate.

*Utility locates- Fiddlehead is responsible for requesting locate (gas, electric, water, sewer).

*Items hidden in ground (tree roots, oil tanks, bedrock, concrete pads, undisclosed irrigation systems, all items not visible above ground) to be disclosed to client upon discovery by contractor. Any work to address such items and will become an extra charge over and above the estimate.

*Existing concrete and asphalt surfaces are prone to cracking under stress of construction. We will take precautionary measures to minimize any possible damage but is not responsible for any repairs.

* We assume all details specified on design have been approved by client. Any changes made once construction begins may disrupt our schedule and may incur additional costs. Please review and approve of all construction details prior to the start of work.

